Location	Specification	Cost
A1068 (West) after Portland Terrace	To supply, deliver and install Arun PITCHED roof cantilever shelter to the following specification:2.64m (2 bay) long x 1.38m wide, 4mm bronze roof polycarbonate, 2mm mesh metal upper panels, 2.5mm solid metal lower panels, mid rails, standard height, 2x full end panel with solid lower and mesh upper panels. Install dig into level site, back of path, new concrete base with pin kerbs as requested, standard give/take traffic management, TM plan and permit application. Removal and disposal of existing shelter including base.	£9,196.25
Next to Wansbeck General Hospital	To supply, deliver and install Arun PITCHED roof cantilever shelter to the following specification:2.64m (2 bay) long x 1.38m wide, 4mm bronze roof polycarbonate, 2mm mesh metal upper panels, 2.5mm solid metal lower panels, mid rails, standard height, 2x full end panel with solid lower and mesh upper panels. Install dig into level site, back of path, standard give/take traffic management, TM plan and permit application. Removal and disposal of existing shelter and seat.	£7,667.25
High Market (South side)	To supply, deliver and install Arun PITCHED roof cantilever shelter to the following specification:2.64m (2 bay) long x 1.38m wide, 4mm bronze roof polycarbonate, 2mm mesh metal upper panels, 2.5mm solid metal lower panels, mid rails, standard height, 2x full end panel with solid lower and mesh upper panels. Install dig into level site, back of path, standard give/take traffic management, TM plan and permit application. Removal and disposal of existing shelter.	£7,667.25
High Market (North side) (Funded by County Cllr Lynne Grimshaw)	To supply, deliver and install Arun PITCHED roof cantilever shelter to the following specification:2.64m (2 bay) long x 1.38m wide, 4mm bronze roof polycarbonate, 2mm mesh metal upper panels, 2.5mm solid metal lower panels, mid rails, standard height, 1x full end panel with solid lower and mesh upper panels. Install dig into level site, front of path, standard give/take traffic management, TM plan and permit application. Removal and disposal of existing shelter and seat.	£7,808.00
A1068 (East) opposite Portland Terrace (Funded by County Cllr Lynne Grimshaw)	To supply, deliver and install Arun PITCHED roof cantilever shelter to the following specification:2.64m (2 bay) long x 1.38m wide, 4mm bronze roof polycarbonate, 2mm mesh metal upper panels, 2.5mm solid metal lower panels, mid rails, standard height, 2x full end panel with solid lower and mesh upper panels. Install dig into level site, back of path, new concrete base with pin kerbs - new tarmac footpath area, standard give/take traffic management, TM plan and permit application. Removal and disposal of existing shelter including base.	£9,417.25
	Total Cost	·
	Town Council Funding	£24,530
	County Cllr Lynne Grimshaw Funding	£17,225